CERTIFICATE OF APPROPRIATENESS

Application Date: August 4, 2023

Applicant: Sam Gianukos, agent for Cody Miller, owner.

Property: 509 Teetshorn Street, Lot 14, Block 24, Woodland Heights Subdivision. The property includes a

historic 980 square foot, one-story wood frame single-family residence situated on a 6,350 square

foot (50' x 127') interior lot.

Significance: Contributing craftsman residence, constructed circa 1920, located in the Woodland Heights Historic

District.

Proposal: Alteration – Addition

The applicant is proposing to construct a 3,104 SF two- story addition with an attached garage. The ridge of the addition will be 28'-9" and the eave height 22'. The applicants proposes the following:

The addition will be clad in new treated smooth Cementous Hardie siding.

All new windows will be inset and recessed.

• The non-original front door will be replaced with a custom Craftsman style wood door.

• Two windows will be removed at the rear of the existing house and will be filled in with siding to match existing.

• The addition will have a 5/12, 6/12 pitch hip, gable roof with material to match existing roof.

See enclosed application materials and detailed project description for further details.

Public Comment: Three letters of support. See attachment A

Civic Association: No comment received.

Recommendation: Deferral

HAHC Action: -

509 Teetshorn Street Woodland Heights

APPROVAL CRITERIA

ALTERATIONS, REHABILITATIONS, RESTORATIONS AND ADDITIONS

Sec. 33-241: HAHC shall issue a certificate of appropriateness for the alteration, rehabilitation, restoration or addition of an exterior feature of (i) any landmark, (ii) protected landmark, (iii) any building, structure or object that is part of an archaeological site, or (iv) contributing building in a historic district upon finding that the application satisfies the following criteria, as applicable:

S	D	NA		S - satisfies D - does not satisfy NA - not applicable
			(1)	The proposed activity must retain and preserve the historical character of the property;
			(2)	The proposed activity must contribute to the continued availability of the property for a contemporary use;
			(3)	The proposed activity must recognize the building, structure, object or site as a product of its own time and avoid alterations that seek to create an earlier or later appearance;
			(4)	The proposed activity must preserve the distinguishing qualities or character of the building, structure, object or site and its environment;
			(5)	The proposed activity must maintain or replicate distinctive stylistic exterior features or examples of skilled craftsmanship that characterize the building, structure, object or site;
			(6)	New materials to be used for any exterior feature excluding what is visible from public alleys must be visually compatible with, but not necessarily the same as, the materials being replaced in form, design, texture, dimension and scale;
			(7)	The proposed replacement of exterior features, if any, should be based on an accurate duplication of features, substantiated by available historical, physical or pictorial evidence, where that evidence is available, rather than on conjectural designs or the availability of different architectural elements from other structures;
			(8)	Proposed additions or alterations must be done in a manner that, if removed in the future, would leave unimpaired the essential form and integrity of the building, structure, object or site;
			(9)	The proposed design for any exterior alterations or addition must not destroy significant historical, architectural, archaeological or cultural material, including but not limited to siding, windows, doors and porch elements;
			(10)	The proposed alteration or addition must be compatible with the massing, size, scale material and character of the property and the context area; and
			(11)	The distance from the property line to the front and side walls, porches, and exterior features of any proposed addition or alteration must be compatible with the distance to the property line of similar elements of existing contributing structures in the context area.



PROPERTY LOCATION

WOODLAND HEIGHTS HISTORIC DISTRICT



INVENTORY PHOTO



CONTEXT AREA



505 Teetshorn Street - Contributing - 1915 (neighbor)



513 Teetshorn Street - Contributing - 1915 (neighbor)



520 Teetshorn Street- Contributing - 1915 (across street)



524 Teetshorn Street- Contributing - 1924 (across street)



519 Teetshorn Street- Contributing - 1915 (neighbor)



523 Teetshorn- Contributing - 1916 (neighbor)

CONTEXT AREA



526 Teetshorn Street- Contributing - 1924 (neighbor)



525 Teetshorn Street- Contributing - 1920 (across street)



MAPS EXISTING AND SANBORN





Figure 1- 1924 Sanborn map



EXISTING PHOTOS











3D VIEWS PROPOSED





Figure 2- southwest view



SOUTH ELEVATION-

FRONT FACING TEETSHORN EXISTING





WEST SIDE ELEVATION

EXISTING



September 14, 2023 HP2023_0192 509 Teetshorn Street Woodland Heights


PROPOSED



EAST SIDE ELEVATION

EXISTING





NORTH (REAR) ELEVATION

EXISTING












SITE PLAN EXISTING









ROOF PLAN EXISTING





FIRST FLOOR PLAN

EXISTING






509 Teetshorn Street Woodland Heights

\leftarrow N

SECOND FLOOR PLAN



WINDOW / DOOR SCHEDULE

\otimes	EXISTING DOOR SCHEDULE								
ITEM	COUNT	SIZE	TYPE	DESCRIPTION					
1	1	3'-0" x 6'-8"	EXTERIOR EXISTING						
2	4	2'-8" x 6'-8"	INTERIOR	EXISTING					
3	1	2'-8" x 6'-8"	EXTERIOR	EXISTING, FRENCH HALF-LITE					
4	1	2'-0" x 6'-8"	INTERIOR	EXISTING					
5	1	2'-4" x 6'-8"	INTERIOR	EXISTING					

$\langle \times \rangle$		EXISTING WINDOW SCHEDULE							
ITEM	COUNT	SIZE	HEADER	TYPE	DESCRIPTION				
Α	12	32" x 62"	7'-0"	SINGLEHUNG	EXISTING TO REMAIN				
В	4	32" x 42"	7'-0"	SINGLEHUNG	EXISTING TO REMAIN				
С	1	32" x 36"	7'-0"	SINGLEHUNG	EXISTING TO REMAIN				
D	1	26" x 42"	7'-0"	SINGLEHUNG	NON-ORIGINAL TO BE REMOVED				
E	2	22" x 42"	7'-0"	SINGLEHUNG	NON-ORIGINAL TO BE REMOVED				

PROPOSED DOOR SCHEDULE							
COUNT	SIZE	TYPE	DESCRIPTION				
1	12'-0" x 8'-0"	EXTERIOR	NEW, SLIDING FRENCH DR - 4 SECTIONS				
1	10'-0" x 8'-0"	INTERIOR	NEW, OVERHEAD				
1	5'-0" x 8'-0"	INTERIOR	NEW, OVERHEAD				
2	4'-8" x 6'-8"	INTERIOR	NEW POCKET DOUBLE				
6	3'-0" x 6'-8"	INTERIOR	NEW				
1	3'-0" x 6'-8"	INTERIOR	NEW, FIRE RATED SELF CLOSING DR.				
1	3'-0" x 6'-8"	EXTERIOR	NEW, CRAFTSMAN DR.				
8	2'-8" x 6'-8"	INTERIOR	NEW				
1	2'-6" x 6'-8"	INTERIOR	NEW POCKET				
11	2'-6" x 6'-8"	INTERIOR	NEW				
3	2'-4" x 6'-8"	INTERIOR	NEW				
	1 1 1 2 6 1 1 8 1	COUNT SIZE 1 12'-0" x 8'-0" 1 10'-0" x 8'-0" 1 5'-0" x 8'-0" 2 4'-6" x 6'-8" 6 3'-0" x 6'-8" 1 3'-0" x 6'-8" 1 3'-0" x 6'-8" 1 2'-6" x 6'-8" 1 2'-6" x 6'-8"	COUNT SIZE TYPE				

$\langle \times \rangle$		NEW WINDOW SCHEDULE							
ITEM	EM COUNT SIZE I		HEADER	TYPE	DESCRIPTION				
NΔ	12	48" x 24"	7'-8"	FIXED	NEW				
NB	18	48" x 24"	9'-8"	FIXED	NEW				
NC	20	35" x 60"	7'-8"	DOUBLE HUNG	NEW				
ND	5	24" x 24"	7'-8"	DOUBLE HUNG	NEW TO BE REMOVED				
ΝE	6	48" x 12"	7'-8"	CASEMENT	NEW - ON SITE				
Ν F	11	31" x 48"	10'-0" - 7'-8"	DOUBLE HUNG	NEW, TEMPERED - ON SITE				
NG	10	24" x 24"	11'-10"	CASEMENT	NEW - ON SITE				
NH	30	35" x 60"	7'-8"	DOUBLE HUNG	NEW - ON SITE				
NJ	20	31" x 60"	7'-8"	DOUBLE HUNG	NEW				
ΝK	5	35" x 60"	7'-8"	DOUBLE HUNG	NEW, TEMPERED - ON SITE				
•									

CERTIFICATE OF APPROPRIATENESS



WINDOW WORKSHEET

	EXISTING WINDOW SCHEDULE									
Window Material		Lite	Style	Dimensions	Recessed/Inset	Original/	Existing to			
		Pattern				Replacement	Remain			
Ex. A1	Wood	1/1	DH	32 x 66	Recessed	Original	No			
Α	WOOD	1/1	SH	32x62	RECESSED	ORIGINAL	YES			
В	WOOD	1/1	SH	32x42	RECESSED	ORIGINAL	YES			
С	WOOD	1/1	SH	32x36	RECESSED	ORIGINAL	YES			
D	WOOD	1/1	SH	26x42	RECESSED	NON-ORIINAL	NO			
Е	WOOD	1/1	SH	22x42	RECESSED	NON-ORIINAL	NO			

	DAMAGE TO EXISTING WINDOWS								
Window	Describe Damage								
Ex. A1	Glass is broke, window is inoperable, rail is rotten, and frame is broken								

	PROPOSED WINDOW SCHEDULE										
Window	Material	Lite	Style	Dimensions	Recessed/	Brand/	Other				
		Pattern			Inset	Vendor					
Ex. A1	Wood	1/1	DH	32 x 66	Recessed	Plygem					
NA	WOOD	1/1	FX	48x24	RECESSED	JELDWYN					
NB	WOOD	1/1	FX	48x24	RECESSED	JELDWYN					
NC	WOOD	1/1	DH	35x60	RECESSED	JELDWYN					
ND	WOOD	1/1	DH	24×24	RECESSED	JELDWYN					
NE	WOOD	1/1	FX	48x12	RECESSED	JELDWYN					
NF	WOOD	1/1	DH	31x48	RECESSED	JELDWYN					
NG	WOOD	1/1	FX	24x24	RECESSED	JELDWYN					
NH	WOOD	1/1	DH	35x60	RECESSED	JELDWYN					
NJ	WOOD	1/1	DH	31x60	RECESSED	JELDWYN					

- Must include photos of all windows with labels indicated on this sheet
- Must include manufacture's specifications and details for all proposed windows

^{***} Use additional sheets as necessary

ATTACHMENT A

LETTERS OF SUPPORT

509 Teetshorn Drawing Reveiw



[This message came from outside the City of Houston email system. Please be careful while clicking links, opening attachments, or replying to this email.]

Ms. Arslan, please see below my letter regarding the plans for 509 Teetshorn.

Meg & Cody -- I appreciate you sharing these drawings with us that you are planning for your future home down the street.

We have loved living on Teetshorn and your plan for remodeling the existing home on the 500 block will be a welcomed addition to the neighborhood.

I have to say that after flipping through the plans, it stands out to me that you have such a welcoming front porch and front yard feel which is a much loved aspect of so many of the homes in this neighborhood.

In looking at the expansion built up towards the rear of the property, it looks to be adding some excellent living space that you'll enjoy while keeping the familiar look and feel of the original homes on these blocks. In particular, this will be well received because the garage and second story addition is set so far back from the street and the front facade of the home. You'll still have the long drive leading back to the garage and the 2nd story addition. This is a nice contrast to some of the other homes that I've seen where the garage and upper level are pulled forward.

I'm not sure how much use you'll be getting from the chimney here in Houston, but it is cool that you're keeping that feature from the home for the 2-3 day a year that it'll be needed - we'll know where to go if we're looking for a fire to keep warm next time a winter blast comes through Houston.

Keep us posted on your progress, and we look forward to having you join us on Teetshorn.

Thanks,



HP2023_0192

